

Automatic Fire Alarm Systems

The Fire Alarm Inspection occurs at the Fire Final. Please reference Fire Final Inspection requirements.

Automatic Fire Alarm Inspection shall include, but not be limited to, the following:

- The system must be pre-tested prior scheduling the acceptance test.
- All initiating devices and all signaling devices will be tested and inspected.
- The City of Frisco Fire Department requires that a water flow alarm be a distinctive and separate alarm.
- All systems are required to be monitored by a UL listed Central Station.
- Construction and final clean-up must be completed prior to scheduling the acceptance test.