



## CITY OF FRISCO PURCHASING DIVISION

November 29, 2011

### **Addendum #1**

**Bid #1211-021**

### **Oakbrook Neighborhood Park Renovations, Phase 2**

#### **Clarifications:**

1. Water restrictions in Stage 3 will allow for new sod to be watered for 30 days. Stage 4 will not allow for watering. Stage 4 probably won't go into effect until spring if that happens.
2. Existing stacked retaining wall will be rebuilt with same materials and must be disassembled to ensure the foundation will be made up on 5 in. of compacted road base and 1 in. of sand. The trench needs to be 24 in. of fill until the full depth has been achieved, then add sand. After the foundation is completed, place  $\frac{3}{4}$  in. stone aggregate in front and behind the blocks to help secure the block and provide drainage through the gravel. This will continue on the back side of the wall all the way to the top. Back fill last 1 foot with soil and apply Bermuda sod equal to the top of the wall. Lastly, place and glue top caps along entire length of wall.
3. On the southeast side of the ball field, bid the 315 LF sidewalk at bottom of slope instead of the top of the slope.
4. The specifications for the bollard detail states "concrete footing by others". This is a note from the manufacturer, not the City of Frisco. Please note on bid form #5 that the contractor will be installing the bollards. The footing depth will be 18"-24" instead of 27".

Vendors who may have already submitted a bid and feel this addendum may change their bid price, may pick up their bid, and return it by the closing date. If picking up the bid is not feasible, any new bid submitted by your firm will supersede one previously submitted.

Acknowledge receipt of this addendum by initialing in the appropriate space on the bid document.

Jean Stelatella, CPPB  
Buyer  
City of Frisco