



## CITY OF FRISCO PURCHASING DIVISION

September 27, 2012

Addendum #1

Bid #1209-081

### **Bicentennial Park Phase II Extension**

#### **Additions:**

- Frisco General Notes have been updated. See Sheet LN101.
- The 10 feet wide reinforced sidewalk is now (6) inches thick to be strong enough to support fire apparatus. That is shown on the SP-series and on the paving details.
- Tree removal and paving removal in the tree wells northeast of the parking lot is called out on the SP-sheets.
- Fire lane striping is now 6" instead of 4". See sheet SP102.
- See sheet LD100 for more sidewalk to demo and replace as part of proposed sanitary sewer line construction.
- Conduit through the pavilion foundation has been called out. See sheet S2.
- A 1" meter has been called out on sheet MP-01

#### **Clarifications:**

- The existing water line and fire hydrant has been shown in approximate location along McKinney Road. See sheet SP100.
- Proposed and existing water service lines have been labeled on SP100.
- A water meter table for the proposed 1" meter was added. See SP100
- The existing sidewalk has been shown along McKinney Road. See sheet SP100.
- The existing sidewalk has been shown in approximate location connecting north of the parking lot. See sheet SP100.
- Notes on LP101 have been made larger for legibility.
- Regarding the SS plan, it has been verified that the manhole is deep enough to meet grade. See CC100.
- Manholes or cleanouts to adequately maintain the service line are shown on CC100.
- Scale on sheet LG100 is 1"=10'-0"
- Scale on sheet LP100 is 1"=10'-0"
- Scale on sheet LI100 is 1"=10'0"

Vendors who may have already submitted a bid and feel this addendum may change their bid price, may pick up their bid, and return it by the closing date. If picking up the bid is not feasible, any new bid submitted by your firm will supersede one previously submitted.

Acknowledge receipt of this addendum by initialing in the appropriate space on the bid document.

Sincerely,

C.S.J.