

ADDENDUM NO. 1
January 28, 2013
Cotton Gin Road (Station 4+17.32 to Station 18+31.94)
Project manual
City of Frisco, Texas
CIP No. 11-0017, Bid 1301-023

Please note the following **CLARIFICATIONS** for the above referenced project:

Item #1	Page 1 - Table of Contents	Special Conditions	SC 1 – 2
Item #2	Page 11 - Section 1	Bid Form	P-16 & P-17
Item #3	Page 17 - Section 1	Bid Form	C-1 Contingency
Item #4	Page SC 1 - Section 2	Special Conditions	SC-6 & SC-7
Item #5	Page SC 2 - Section 2	Special Conditions	SC-9
Item #6	Testing: CONTRACTOR shall pay for and be responsible for all testing as required by the City of Frisco. The cost of all testing shall be included in all unit prices and shall not be considered an additional pay item.		
Item #7	General Subsurface Conditions: The Project site lies in area of alluvial and fluvial deposits associated with Trinity River system, underlain by the Eagle Ford Formation.		
Item #8	Power Pole Cables: The City of Frisco is coordinating with CoServ on the relocating of the conflicting cables.		
Item #9	Curb Inlets: The Curb Inlet shall be poured in place as per City of Frisco specification #033105.		
Item #10	<p>*Lime Series Calculation: $10.5\% (.105) \times 106 \text{ (avg. dry wt.)} \times 9 \text{ SF} = 100.17\text{\#/SY}$ $\frac{5,750 \text{ SY LSS} \times 100.17\text{\#/SY}}{2,000 \#} = 288 \text{ Tons of Lime}$</p> <p>* Average Dry Weight to be confirmed in field by Geotechnical Engineer prior to application of Lime.</p>		
Item #11	Pavement Stripping: All pavement stripping shall consist of Thermo paint as per City of Frisco specification #321723.		
Item #12	Delete Line Item L-2: Lighting not required.		

The above listed items are hereby made a part of the Bid Documents for Cotton Gin Road (Station 4+17.32 to Station 18+31.94) CIP 11-0017, Bid 1301-023, City of Frisco, Texas..