

Aboveground Automatic Fire Sprinkler Systems: Residential

Above Ground Automatic Fire Sprinkler Systems: Residential Inspection shall include, but not be limited to, the following:

Must be requested by the installing contractor.

Verify completion of underground inspections prior to stacking riser.

Hydrostatic Test:

- Minimum 200 psi for two hours. No pressure drop allowed.
- The system must be left uncovered and visible from the floor.
- All freeze protection; fire caulking and nail plates must be installed at time of hydrostatic test.
- Underground supply must be in place at time of hydrostatic test.
- Must obtain fire sprinkler inspection prior to framing inspection from Developmental Services.